



# TMC SPECIFICATION

NO. S1384

REV:

COMPILED:

CHECKED:

APPD:

SHEET

OF

TITLE:

## DD116-2 Inspection Check

### MECHANICAL INSPECTION

Insure all hardware is fasten securely - - - - - \_\_\_\_\_

Insure electrical connections are  
fasten securely to terminals - - - - - \_\_\_\_\_

Insure for total construction rigidity - - - - - \_\_\_\_\_

### ELECTRICAL INSPECTION

Test Equipment Required  
Simpon 260 meter or equivalent.

(use scale RX 10,000)  
With probes properly placed for each diode  
plus to plus and minus to minus meter  
should read infinite - - - - -

Diode 1 \_\_\_\_\_  
Diode 2 \_\_\_\_\_

Reversing probes, meter should  
read approximately 150,000 ohms - - - - -

Diode 1 \_\_\_\_\_  
Diode 2 \_\_\_\_\_

Tested by: \_\_\_\_\_

Mfg. No.: \_\_\_\_\_

Date: \_\_\_\_\_