



DATE	8-17-64	TMC SPECIFICATION NO. S-706	A
SHEET	1 OF 4		
RM COMPILED	 CHECKED	TITLE:	
JG APPROVED			

A-1397 POWER SUPPLY, FOR SBE  
PRODUCTION TEST PROCEDURE

DATE	8-17-64	TMC SPECIFICATION NO. S-706	A
SHEET	2 OF 4		
COMPILED	CHECKED	TITLE: A-1397 Power Supply, for SBE- Production Test Procedure	
APPROVED			

**TEST EQUIPMENT REQUIRED**

- a. TMC Model SBE- sideband exciter.
- b. Ballentine VTVM 314.
- c. Simpson VOM 260.
- d. Interconnecting cable TMC CA-346/3FT/F.
- e. AC power cable TMC CA103-72

**A. Preliminary:**

- 1. Inspect the unit to be tested for wiring errors, electrical connections and correct value of fuses.

**B. Electrical Tests:**

- 1. Connect cable CA-346 from J-109 on the SBE- to J-402 on the unit to be tested and the AC power cord CA-103 from the AC input of the power supply to a 115 V AC outlet.
- 2. Place Power and Exciter switches in ON position. All other controls on the SBE- OFF or at minimum position.
- 3. After 5 minutes warm up utilizing the VOM take voltage readings indicated below, parents a thru g. Use the VTVM for the voltage readings below, paren h.
  - a. Check voltage on pin 5 of C-402, it should be 250 VDC,  $\pm 10\%$ .
  - b. Check voltage on pin 5 of C-403, it should be 180 VDC,  $\pm 10\%$ .
  - c. Check voltage on pin 3 of C-403, it should be 225 VDC,  $\pm 10\%$ .
  - d. Check voltage on pin 1 & 5 of V-402, it should be 150 VDC  $\pm 5\%$ .
  - e. Check voltage on pin 4 of T-402, it should be 6.3 VAC  $\pm 5\%$ .
  - f. Check voltage on pin 5 of T-401, it should be 6.3 VAC  $\pm 5\%$ .
  - g. Check voltage on pin 9 of T-401, it should be 6.3 VAC  $\pm 5\%$ .

**NOTE:** Indicate completion and acceptance of portion(s) of this test procedure by (\*) by recording required observed value or by check (✓) mark as required on attached test Data Sheets.

DATE <u>8-17-64</u>		<b>TMC SPECIFICATION NO. S-706</b>	<b>A</b>
SHEET <u>3</u> OF <u>4</u>			
COMPILED	CHECKED	TITLE: <b>A-1397 Power Supply for SBE- Production Test Procedure.</b>	
APPROVED			

h. Check ~~max~~ level with the AC VTVM at Pin 1 & 5 of V-402. It should not exceed .02 V.AC.

4. To check fusing circuits, perform the following:-

- a. Pull out B+ fuse. The EXCITER light on the front panel will go out.
- b. Pull out the MAIN power fuse. The power light on the power supply will go out.
- c. Pull out the OVEN fuse. The OVEN light on the front panel will go out.

NOTE: Indicate completion and a portion of this test procedure by (\*) by recording required observed value or by check (✓) mark as required on attached test Data Sheets.

DATE <u>8-17-64</u>	<b>TMC SPECIFICATION NO. S-706</b>	A
SHEET <u>4</u> OF <u>4</u>	TITLE: <b>A-1397 Power Supply, for SBE- Production Test Procedure</b>	
COMPILED _____	CHECKED _____	<b>TEST DATA SHEET</b>
<b>APPROVED</b>		

1. (A) Preliminary inspection completed \_\_\_\_\_ (✓)
2. (B) Electrical tests:-
- | <u>Volt. Reading Point</u> | <u>Requ't</u>         | <u>Result</u> |
|----------------------------|-----------------------|---------------|
| a. Pin #5, C-402           | 250 VDC $\pm$ 10%     | _____ VDC     |
| b. Pin #5, C-403           | 180 VDC $\pm$ 10%     | _____ VDC     |
| c. Pin #3, C-403           | 225 VDC $\pm$ 10%     | _____ VDC     |
| d. Pin #1 & 5, V-402       | 150 VDC $\pm$ 5%      | _____ VDC     |
| e. Pin #4, T-402           | 6.3 VDC $\pm$ 5%      | _____ VDC     |
| f. Pin #5, T-401           | 6.3 VDC $\pm$ 5%      | _____ VDC     |
| g. Pin #9, T-401           | 6.3 VDC $\pm$ 5%      | _____ VDC     |
| h. Pin #1 & 5, V-402       | Net to exceed .02 VAC | _____ VAC     |
3. (4) Fusing circuit checks completed \_\_\_\_\_ (✓)

Mfg. No. \_\_\_\_\_ Ser. No. \_\_\_\_\_ Date \_\_\_\_\_

Tested by \_\_\_\_\_ Approved by \_\_\_\_\_

Remarks:

DATE 8-17-64  
SHEET 4 OF 4

# TMC SPECIFICATION NO. S - 706

COMPILED \_\_\_\_\_  
CHECKED \_\_\_\_\_

TITLE: A-1397 Power Supply, For SBE-3  
Production Test Proc dur

APPROVED \_\_\_\_\_

## TEST DATA SHEET

1. (A) Preliminary Inspection Completed \_\_\_\_\_ (✓)

2. (B) Electrical Tests:-

<u>Volt. Reading Point</u>	<u>Reqm't</u>	<u>Results</u>
a. Pin #5, c-402	250 VDC $\pm$ 10%	_____ VDC
b. Pin #5, c-403	180 VDC $\pm$ 10%	_____ VDC
c. Pin #3, c-403	225 VDC $\pm$ 10%	_____ VDC
d. Pin #1, & 5, V-402	150 VDC $\pm$ 5%	_____ VDC
e. Pin #4, T-402	6.3 VAC $\pm$ 5%	_____ VAC
f. Pin #5, T-401	6.3 VAC $\pm$ 5%	_____ VAC
g. Pin #9, T-401	6.3 VAC $\pm$ 5%	_____ VAC
h. Pin #1 & 5, V-402	Not to exceed .02 VAC	_____ VAC

3. (4) Fusing circuit checks completed \_\_\_\_\_ (✓)

Mfg. No. \_\_\_\_\_ Ser. No. \_\_\_\_\_ Date \_\_\_\_\_

Tested by \_\_\_\_\_

Approved by \_\_\_\_\_

Remarks:

